APPENDIX 1

INTERIOR DESIGN SCOPE OF SERVICES

B. DESIGN DEVELOPMENT

A. PROJECT DESCRIPTION

Amidst 65 acres of lush landscaping along a private coastline, One&Only Royal Mirage is a luxury resort. Overlooking The Palm and celebrating the splendour and opulence of Arabia, the resort is composed of three distinct resort environments: The Palace, Arabian Court, and the Residence & Spa. Each of the areas complements each other through Arabic design, heritage, and hospitality. The resort conjures the legends of Arabia combined with the modern backdrop of the Palm Island Bay and Dubai Marina skyline, effortlessly combining the traditional with the contemporary. just minutes from the buzzing city, the luxury retreat offers the perfect sanctuary to discover Dubai from hot air balloon trips across the desert to chartered boat trips to unseen stretches of the Arabian Gulf.

Hotel Information: Luxury Hotel-5 stars

Location: King Salman Bin Abdulaziz Al Saud St - Dubai Marina

B. SCOPE OF SERVICES FOR INTERIOR DESIGN

The Consultant [also referred to as "Service Provider" in the Service Agreement] shall provide Interior Design services to the areas mentioned below in coordination with the Client. The Consultant will be required to illustrate through drawings, renderings, materials, and finishes the full interior design presentation and obtain approval from (Wasl& Kerzner formal sign off) for each stage submittal and produce the relevant interior design documentation for the areas mentioned below.

The scope of services to be performed and successfully completed by the Consultant to the final satisfaction of the Client and in accordance with the agreement shall include but not limited to the following stages:

- Stage 1: Data Collection
- Stage 2: Concept Design
- Stage 3: Schematic Design
- Stage 4: Draft Detailed Design & Tender Documents
- Stage 5: Final Detailed Design & Tender Documents

The Consultancy Fee proposal breakdown and program for delivery of the Services shall be submitted for the above stages accordingly.

INSTRUCTIONS TO PROCEED WITH STAGES 1 TO STAGE 5

The Client shall instruct to proceed with Stage 1 to Stage 5 only upon the approval of the Stage 1.

1.0 STAGE 1: DATA COLLECTION, PREPARATION WORK & FINALIZATION OF PROJECT DESIGN BRIEF

The Consultant shall collect all relevant data together with approved architectural base plans and sections and ascertain in conjunction with the Client the Project requirements and shall include obtaining the Operators requirements & DCTM requirements in the case of a Hotel & Serviced Apartments or similar type of projects. These shall include the following but should not be limited to:

- Preliminary Space Allocation.
- Briefing report as provided in the RFP.
- Review of the Clients rules and regulations.
- Review of the Operators guidelines if relevant to project.
- Review of DCTM requirements if relevant to project.
- Designation of users.
- Special equipment and systems.
- Prioritize the design objective.

1.1 PROJECT DESIGN BRIEF

The Consultant shall perform a detailed review of the brief as provided in the RFP and conduct a workshop with the Client to prioritize the Interior Design objectives. Following this workshop a briefing report shall be generated by the Consultant and signed as the official final detailed briefing document. Various concept options may be sketched and explored to help define the final brief.

The Consultant shall, in close collaboration with the Client, finalize the Interior Design Brief and guidelines.

2.0 STAGE 2: CONCEPT DESIGN COMPLETION

The Consultant shall collect all relevant data together with approved architectural base plans and sections and ascertain in conjunction with the Client the Project requirements and shall include obtaining the Operators requirements & DTCM requirements.

These shall include the following but should not be limited to:

- Revalidate the Concept design approved in Stage 1 and develop the design narrative, accordingly, including all the areas mentioned above.
- Establishing Client's requirements.
- Space Planning.
- Carrying out Feasibility studies of Client's requirements against constraints.
- Including Lighting design, Artworks, Signage & Wayfinding.
- Implementation of all Authority regulations and requirements.
- Acknowledging budget constraints as per BAF.
- Preliminary Cost Estimate.
- Producing enough 3D visuals to explain the concept.

The objective of this design stage is analysis of the Client's requirements, offering concept design proposals essentially to determine a general coordinated approach to layouts & design to obtain the authoritative approval of the Client.

2.1 Interior Design Scope

The Consultant shall:

- Analyze Client's Requirements; Develop and verify concept Design Data.
- Acknowledge the budget restraints.
- Develop perspectives based on the selected mood of areas selected by the client.
- Consider space definition, flexibility, wayfinding, and strategies for integrating architecture, lighting, MEP, and other disciplines relevant to the project.
- Allow for three (3 nos.) design revisions.
- Concept layout to take full consideration of the following project specific constraints:

1. Interface of internal partitions to façade to be coordinated.
2. Localized changes to room planning to accommodate the shifting of the floor plate relative to the core and use of potential dead spaces.

- Prepare initial cost plan for the clients review and approval.

2.2 Deliverables:

Deliverables shall include but not necessarily be limited to the following topics:

1. Twenty (20 nos) color photorealistic visuals of the following areas, but not limited to them, with proposed major materials:
   1. Concept layouts, space planning and lighting design.
   2. Concept Signage and Wayfinding.
   3. Overall plans for each floor highlighting the areas in scope.
   4. Project program for deliverables.
   5. Concept cost estimate.
   6. Material Boards for each area.

2.1 Concept Design Completion Report

At the completion of Stage 2, the consultant shall make a full presentation of the Concept Design to the Client. Following the presentation, the Consultant shall prepare a Concept Design Completion Report and will be submitted to the Client for review and approval of one concept, final visuals & material boards to be revised incorporating Wasl's comments.

The consultant shall remain responsible for submitting all the deliverables in this document incorporating Wasl's final comments including and not limited to drawings, reports, BOQ's, estimated cost of the proposals, visuals, material boards …etc.

3.0 STAGE 3 – SCHEMATIC DESIGN

3.1 Introduction

The goal of this phase is to develop the preferred design strategy selected during Concept Design. Schematic Design (SD) will focus on the preparation of fully coordinated (Structural, MEP and Lighting) general arrangement drawings for submission for review/approval by the Client's. Project support data from all disciplines shall be coordinated and available together with outline specifications and an update of the cost plan in accordance with the concept cost estimate. At the conclusion of this stage the Consultant is required to submit a full explanatory report for review and approval.

3.2 Interior design scope

The Consultant shall:

- Revalidating the Concept Design is required by the Client.
- Develop schematic layouts for all areas from the selected option.
- Develop internal plans, sections, elevations and establish spatial requirements in terms of dimensions and ceiling heights.
- Develop Lighting design, Artworks, Signage & Wayfinding

- Provide data & coordinate with others such as Hotel Operator, DTCM, Architectural and Engineering disciplines.
- Select schedule of finishes and prepare outline specifications. Finalize the programme for fit-out.
- All specifications of materials, equipment, furniture, finishes etc. shall be with proven performance and shall ensure high performance and the capability of withstanding repetitive abuse by users. Project specifications shall also include performance specifications of custom manufactured assembled systems. Specifications of materials shall also be based on being 'maintenance friendly'.
- Perform checks against the approved Concept Cost Plan.

3.3 The deliverables:

Deliverables shall include, but not limited to the following:

- Schedule of Drawings
- Final Interior design layouts include overall dimensions and direction of each areas.
- All layouts include legends of finishes and fixtures.
- Floor plan indicating floor finishes, patterns, floor boxes, drains, levels, details etc.
- Furniture layouts.
- Reflected ceiling plans in coordination with MEP fittings incorporating the following:
  a) Ceiling levels, finishes, dimensions, legend and location of all MEP fittings.
  b) Lighting layouts with lighting schedules
  c) Coordination with ELV consultant for integration of GRMS, IT and others
  d) Electrical and Data (small power) layouts indicating the locations of switches, sockets, data outlets, power, telephone points etc.
- Final color rendered layouts and sections/elevations.
- Final 3D visuals
- Final material boards
- List of supplier and relevant resources
- Tender Documentation for mock-up
- Schematic Design Cost Estimate

3.4 Schematic design report

At the completion of Stage 3, the Consultant shall make a full presentation of the Schematic Design to the Client. Following the presentation, the Consultant shall prepare a schematic design report and will be submitted to the client for review and approval.

4.0 STAGE 4: DRAFT DETAILED DESIGN

4.1 Introduction

Draft Detailed Design shall take the form of fully coordinated design of all components of the Project and complete cost checking of the designs for compliance with the approved budget.

The Consultant shall prepare all requisite documents to obtain all approvals and permits from all Service Authorities having jurisdiction over the Project. The Consultant shall release drawings and specifications to review the documents and to facilitate the preparation of the Bill of Quantities. The Consultant will provide direction and assistance in the preparation of a Mockup room. This includes

assistance in procurement of the works, tender activity participation, offer review and evaluation, and site visits to monitor the quality and progress of works.

The Draft Detailed Design shall comprise detailed and fully coordinated Drawings, Finishes Schedules, Specifications, and other Documents as mentioned below.

4.2 Deliverables:

As mentioned earlier, a formal submission is required by the Consultant, which will complement the information contained in the architectural submission. This includes design information not limited to the following.

- Schedule of drawings
- All layouts to Include legends of finishes and fixtures.
- Final interior design layouts include overall dimensions and dimensions of each area.
- Floor plans Indicating floor finish, setting pattern, floor boxes, drains, levels, details, thresholds etc.
- Furniture layouts.
- Reflected ceiling plans & details in coordination with MEP fittings incorporating the following: Ceiling levels, finishes, dimensions, legend, and location of all MEP fittings (AC grilles, light fittings, access panels, smoke detectors, sprinklers ... etc.) All exposed fittings & finishes to be reviewed & approved.
- Lighting layouts with legend incorporating lighting consultant references.
- Electrical power, IT and AV layouts indicating the location of switches, sockets, data outlets, power, and telephone points etc. & including finishes specifications.
- Large scale typical interior details and miscellaneous decorative details

- Floor, wall, and ceiling details and finishes of all areas.
- Elevations/ sections with dimensions
- Drawings and details of:
  1. Partition type and general details.
  2. Casement works types and general details.
  3. Woodwork types and general details.
  4. Metal work type and general details.
  5. Counter and vanity top details.
  6. Kitchen Cabinets.
  7. Built in furniture.
  8. Glass & Mirror work type & general details.
  9. Staircase & ramps details & finishes.
  10. Balustrade & handrails details & finishes.

- Door details and openings schedule.
- ironmongery schedule and general details.
- Lift interior finishes and details.
- Escalator finishes & details.
- Signage Schedule & specifications.
- Finishes Schedule.
- Schedule of required sample/mockup features required.
- Room Data sheets (if required).
- FF&E.
- Curtains, drapes, and furniture fabrics (if required).
- Light fixtures, decorative lighting, switches, and sockets.
- Artwork and accessories.

- Sanitary ware fittings, fixtures, and accessories
- Final framed boards of color rendered perspectives of all areas (revised and updated as per Clients' comments during the previous stages)
- Final color rendered layouts and section/elevations of typical areas.
- Draft Specification book including specifications of all finishes materials, fixtures, artwork & accessories, ironmongery, and FF&E Etc.
- List of suppliers' contacts and relevant resources.
- Draft Detail Design Cost estimate.

4.3 DRAFT FINAL SPECIFICATIONS - INTERIORS

The Consultant shall prepare and submit, in formats agreed with the Client, specifications for all interior Design components of the Project. These shall include quality control requirements, product detail technical specification and execution and workmanship requirements. Depending on the procurement strategy, the relevant specifications for fit-out elements may be incorporated into the Contractor Tender Documents.

All specifications of materials, equipment, Furniture, finishes etc. shall be with proven performance and shall ensure high performance and the capability of withstanding repetitive abuse by users. Project Specifications shall also include performance specifications of custom manufactured assembled systems. Specifications of materials shall also be based on being 'maintenance friendly'.

5.0 STAGE 5: FINAL DETAILED DESIGN & TENDER DOCUMENTS

Following approval of the Draft Detailed Design, the Consultant shall prepare and submit the Final Detailed Design & Tender Documents incorporating the Clients' review comments of the previous stage.

The Final Detailed Design & Tender Documents shall comprise suitably detailed and fully coordinated drawings, specifications, and other documents.

Deliverables for Final Detailed Design & Tender Documents phases shall include but not necessarily be restricted to:

- Final set of Drawings.
- Final Specification book.
- Final Cost Estimates.
- Final Bill of Quantities.

CLOSE OUT REPORT

At the end of Stage 5 a close out report (A3) should be prepared and submitted to the client Including the following but not limited to:

- Content index.
- Full set of drawings.

- Full specifications.
- Final perspectives.
- Images of the material boards.

C. NOMINATION TO A LEAD CONSULTANT

The Client reserves the right to nominate the ID Consultant to work as the ID Sub-consultant and provide the Services under a lead Consultant appointed by the Client. The Service Provider shall, whenever required to do so by the Client, enter into an Agreement with the lead Consultant and shall execute and deliver an Agreement to the Client within 28 days of the Client's request to do so.

D. COPYRIGHT

Wasl has a policy of supporting local industries & prefers not to import manufactured goods that can be produced locally. To that end, the specifying of customized items for FF&E is encouraged to avoid the issues of copyright. It is required that the Designer specify items designed specifically for the project or to modify items in order to indemnify and hold harmless the owner/agent against any damage, loss, claim or liability arising as a result of any claim by any third party alleging that the product provided by the Contractor pursuant to these specifications violate any copyright or any other proprietary rights of any third party.

E. SUBMISSION OF DOCUMENTS & DRAWINGS:

The Consultant is required to submit all project reports, drawings (CAD & PDF) and documents in the format listed below and recorded on computer media using software and formats standardized and approved by the Client. The Consultant is to obtain the Client's approval on format prior of the submission. The rendering should be high quality rendered images at '300 DPI' resolution (or of equivalent value).

	Description	***No***	***Size***
2	**Data Collection, Preparation Work and Finalization of Project Design Brief**		
-	Draft reports	2	A4
-	Final reports	2	A4
-	Electronic File of the Final Report	1	
3	**Concept Design**		
-	Draft reports	2	A4
-	Draft drawings	2	A2
-	Final Report	2	A4
-	Final Drawings	2	A2

-	Colour rendered perspective set (according and not limited to the areas above mentioned)	1	A2
-	Reduced final drawings & perspective in book form	2	A3
-	Mood boards	1	A2
-	Material Boards	1	
-	Project Interior Design Programme	2	A3
-	Initial cost plan	2	A4
-	Electronic File of all the above	1	
4	**Schematic Design**		
-	Draft Reports	2	A4
-	Draft Drawings	2	A1
-	Draft material boards of each area	1	A2
-	Reduced final schematic drawings	2	A3
-	Final reports	2	A4
-	Final schematic drawings	2	A1
-	Mounted Coloured drawings and perspectives	1	A2
-	Mockup Tender Documents (if required)	2	A4
-	Animated Visualization (Optional)	1	
-	Cost plan	2	A4
-	Electronic File of all the above		
5	**Draft Detailed Design**		
-	Draft Detailed Design Drawings	2	A1
-	Draft Specification Book & Schedules	2	A4
-	Draft Reports	2	A4
-	Reduced Draft Final Drawings	2	A3
-	Final Draft Design Drawings	2	A1
-	Final Reports	2	A4
-	Final color rendered perspectives	2	A2
-	Final material boards	1	A2
-	Cost Estimate	2	A4
-	Electronic File of all the above	1	A

Classification: Shared - Confidential

6 Detailed Design & Final Tender Document

-	Draft Final Drawings		
-	Draft Final Specification Book & Schedules	2	A1
-	Draft Final Reports	2	A4
-	Reduced Draft Final Drawings	2	A4
-	Final Drawings	2	A3
-	Final Specification Book	2	A1
-	Final Reports	2	A4
-	Final Cost Estimate	2	A4
-	Final Sales Manuals	2	A4
-	Close out report	2	A3
-	Electronic File for all the above	1	A4

6.0 LIST OF SUB-CONSULTANTS

The ID Consultant to ensure that all the deliverables are coordinated with specialist sub-consultants, but not limited to the following:

1. Signage Consultant
2. Artwork Consultant
3. Lighting Consultant

Renders Requirements: -

Area	Room	Render	Sample Board
One Bedroom	Bedroom	2	1
	Living Room	2	1
	Bathroom walk-in	2	2
	Bathroom Shower area/WC	1	
Entrance Area		3	1
Lounge Area		2	1
Corridors	Passageway	3	2

Total No's of renders/CGI's: 20No's
Total No's of material boards: 8No's
***Consultant to price additional rende s**